MERICH

38

28 25

6½

10


TUCCI[™] 6638

Always check the website for the most updated specifications: www.americh.com





Tub pictured with optional waste & overflow

Builder Series



Platinum Series






Luxury Series








LEGEND:	P PUMP	B BLOW	'er 🗢	JET 💿	ROTARY JET
		🤴 LIGHT	ON/OFF	CONTROL	
I	GRAB E	BAR	ACCESS P	ANEL (MINIM	UM 16" X 20")

INSTALLATION TIPS

- Install according to Owner's Manual and local codes.
- Airbath III units may be 11/2" 21/2" higher than stated.
- Any whirlpool or Airbath unit requires an access panel.
- Hot water supply should be 65-75% of tub capacity or greater.
- Always consult your local plumber for recommendations as installations will vary.
- Cut-out dimensions: Americh recommends waiting until the actual unit is received.



All bathtub dimensions are ± 1/2"

DIMENSIONS

66" x 38" x 22" (1676 x 965 x 559 mm) Whirlpool Operating Gallons = 55 (Liters = 208) Gallon to Overflow = 70 (Liters = 265)

MATERIAL: Acrylic (All Americh Standard Colors)

TUB FLOOR: Textured

UNDERMOUNT: Yes

- Advise Americh when ordering to ensure there are no issues with deck mounted controls.
- Always take dimensions directly from the unit.

ELECTRICAL REQUIREMENTS

Americh recommends one 20 amp ground fault circuit interrupter (GFCI) for each power supply provided with the bathtub.

OPTIONAL ACCESSORIES

- Chromatherapy^{*}
- Grab Bars: 9"
- High Density Insulation*
- iBath Sound System
- Inline Heater (whirlpool only)
- Jets: Additional or Rotary*
- Lo Profile Tub Edge
- Ozone System (whirlpool and/or Airbath only)
- Pillow: 13" *
- Remote Control Upgrade (select series only)
- Serenity Soak (tub only)
- Serenity Soak (tub only)
- Trim Kit Upgrade*
- Waste & Overflow
 - Cable Drive Overflow^{*}

*Standard on Platinum Series

CODES AND COMPLIANCE

Americh products meet or exceed the following standards:

- Underwriters Laboratories (UL)
- Underwriters Laboratories Canada (cUL)
- Canadian Standards Association (CSA)
- ANSI Z124.1 ANSI A112-19.7
- ANSI A112.19.8 ASTM F462-79
- Contact Americh for additional approvals.